

Electric Construction System Hardening (SRIP 6)

Clarifying Questions and Responses #3

April 6, 2026

This Clarifying Questions and Responses #3 consists of 2 pages (all 8.5" x 11").

It is the responsibility of the proposer to assure and guarantee that the proposer has received the Response in its entirety and that the Bidder accepts all conditions contained herein.

Question 1.1

Do any of the circuits we are working on have any capability of loop feeding to eliminate outages on customers if needing any outages.

Response 1.1

There is minimal loop/parallel capability on both sections. Planned outages will be allowed, however any work that can safely be done energized should be planned.

Question 1.2

Location 12 on the Ponderosa has a natural spring or pears to be, is there any variances here that need to be addressed (Matting, Environmental, Digging, etc.)

Response 1.2

Contractor will need to work with the Town of Truckee on permitting and how to address location 12.

Question 1.3

On Commercial load do you want the bid to include possibly do this work at night or weekend or do we just bid it in our regular schedule, and we will cross that at the time.

Response 1.3

Planned outages on commercial load will be allowed as long as 5 days notice is given. This is a lump sum bid, overtime is not determined by the District.

Question 1.4

Spreading the dirt in residential area – should we consider just removing this dirt and disposing of this offsite to keep any issues with residence.

Response 1.4

Contractors will need to work with the residence. The District rarely encounters problems.

Question 1.5

Will there be any need for permits for placer county for the work being performed on Silver Fir Dr.

Response 1.5

The Town of Truckee is the permitting agency.

Electric Construction System Hardening (SRIP 6)

Clarifying Questions and Responses #3

April 6, 2026

This Clarifying Questions and Responses #3 consists of 2 pages (all 8.5" x 11").

It is the responsibility of the proposer to assure and guarantee that the proposer has received the Response in its entirety and that the Bidder accepts all conditions contained herein.

Question 1.6

If plate anchors are needed how do you want the back fill, with the natural back fill or due you want the same materials for the pole hole back fill?

Response 1.6

Natural soil is ok as long as it is compacted.

Question 1.7

Location 20, 21 the wire map calls for 1/0 wire to be installed but the install sheets call out 397 possibly just an error or miss reading it on our side just want to clarify what is needed in field.

Response 1.7

Locations 19 to 20, and 20 to 21 will have 1/0 4wire installed. Construction location notes to be updated after contract award.

Question 1.8

Do we need to spell out the extra work needed on each pole type for example on Ponderosa Dr Map1 Loc. 6 is a C2 but has a primary riser with Line disconnects, will this have an equipment arm for the disconnect switches along with the arm for the pot heads or with the still be inline disconnects and if so is the covers for these as well.

Response 1.8

Construction location notes to be updated to reflect all riser and equipment arm requirements after contract award. Project totals are on the first page summary sheet. Location 6 update was missed during last addendum but is included in project summary.